BENGALURU CENTRAL CITY CORPORATION
O/o, Executive Engineer (MPED&Transport), BCCC, Ground floor, Annex building-2, GBA HO Premises N.R.Square, BBMP, Bengaluru-560002

No. E.E/MPED&Transport/QTN/01/2025-26
Date:23.02.2026

SHORT TERM QUOTATION NOTIFICATION FOR RATES

Quotation is invited from the reputed agencies / Suppliers / Distributors /Contractors for the following items The interested supplier/agencies are requested to submit/upload their quotation **through KPP-Portal** on or before **03.03.2026 at 5:30 pm** as detail in the table indicated below, the quotation shall be opened on **14.03.2026 at 5:30 pm.**

Sl.	Particulars	Unit	Qty
1	Providing and fixing of **veneer paneling** over the 50mm x 35mm sal wood frame work and top covered out of 4mm thick approved veneer fixed over 12mm ply finished in mealamme polish, complete including cost and conveyance of all materials, TW beading, labour for all items of work HOM of equipment etc., complete as per specification	Sqm	1
2	Providing and fixing of **"Inspiro sheet"** over the 50mm x 35mm sal wood frame work and top covered with line of high-pressure decorative laminates (Inspiro sheet), Surface Finish: Matte, Textured, High Gloss, or Suede approved Inspiro sheet fixed over 12mm ply complete including cost and conveyance of all materials, TW beading, labour for all items of work HOM of equipment etc., complete as per specification	Sqm	1
3	Providing and fixing of **"funder max panels"** over the 50mm x 35mm sal wood frame work and top covered with 6mm thick durometer high pressure laminates (HPL) in accordance with EN 4386 type EDF produced in lamination presses under great pressure and high temperature double hardened acrylic PUR resins which provide extremely effective weather protection particularly suitable for long	Sqm	1

Sl.	Particulars	Unit	Qty
	asting balconies and facade claddings. fixed over 12mm ply complete including cost and conveyance of all materials, TW beading, labour for all items of work HOM of equipment etc., complete as per specification Providing and fixing of founder max exterior panels of		
4	Providing and fixing of **"Aluminium Composite fluted louvers Panel" Fluted (or corrugated) profiles create depth, texture, and a contemporary, sleek aesthetic** panel over the 50mm x 35mm sal wood frame work and top covered with 4mm thick Aluminium Composite Panel (ACP) fluted louversfixed over 12mm ply complete including cost and conveyance of all materials, TW beading, labour for all items of work HOM of equipment etc., complete as per specification Providing and fixing of founder max exterior panels of	Sqm	1
5	Providing and fixing in position fully 40mm thick Teak wood shutters for doors as per drawing and design issued by Architect and fixing of 4mm thick brass plate as shown in the drawing including cost of materials, labour, HOM of machineries complete as per specifications. (Including cost of fixtures & Polishing) as per the directions of the Engineer in charge of the work with all lead and lift.	Sqm	1
6	Providing Teak wood frames of doors, windows, clerestory windows, ventilators and other frames, wrought, framed or assembled including making plaster groves (excluding cost of cement concrete and side clamps), but including cost of materials, labour, usage charges complete as per specifications.	Cum	1
7	Supplying and installation of approved **wooden floor** (Engineerng wood) for indoor hall Maple flooring with PU Sealer and court polish 20mm thick x60mm width x 2000mm, third and better grade trated sleepers of size 30x60mm to be installed 30cm c/c 20mm professional EPDM rubber pad inclusive of HOM, labour, etc. as per the directions of engineer-in-charge	Sqm	1
8	Supplying and installation of approved **Click N Lock floor tiles (wood, stone, or marble finishes) Stone Polymer Composite (SPC) flooring designed for rapid, glue-free installation over existing hard surfaces. They typically feature a multi-layer rigid core construction that is 100% waterproof and highly resistant to scratches and stains** for indoor hall which allows the tiles to fit into	Sqm	1

Sl.	Particulars	Unit	Qty
	one another in a unique locking mechanism that removes the need for glue and cement, making the installation process dust and noise free. including cost and conveyance of all materials, TW beading, labour for all items of work HOM of equipment etc., complete as per specification		
9	Providing and fixing of Aluminium **Ventilated Fin louvers cladding 2440mm(L)x35mm(W) x 70mm(H),Tolerance: +5mm** over the 50mm x 35mm sal wood frame work and top covered out of 4mm thick approved veneer fixed over 12mm ply finished in mealamme polish, complete including cost and conveyance of all materials, TW beading, labour for all items of work HOM of equipment etc., complete as per specification	Mtr	1
10	Supply & Installation of Acoustical Wooden Wall panels with 1st layer Wood framing @ 600x600 c/c using 50x50mm Pine Wood with insulation of 50mm thick 1000GSM Polywool synth 2nd layer 8mm Plywood with 50mm dia holes @ every 150 c/c, 3rd layer Wooden Slats of ANUTONE/NISHABD/ARMSTRONG made of pine wood E1 grade fiberboard, melamine laminated finish, groove perforated slats L60 (2mm Slats @16mm pitch) backlined with Soundtexblack acoustical fleece of 0.27mm thick, surface density 63g/m2, tongue-groove edge for a seamless look,, size 128x2440x15mm, volume density of base board 800Kg/m3, weight 9Kg/m2 (L60). as per the directions of the Engineer in charge of the work with all lead and lift.	Sqm	1
11	Supply & Installation of Acoustical Wooden Wall panels with 1st layer of Pine wood Framing @ 600x600 c/c using 50x50mm section pine wood with insulation of 50mm thick 1000GSM Polywool synth 2nd layer 8mm Plywood with 50mm dia holes @ every 150mm c/c. 3rd layer Plywood with laminate finish as per design and drawing with all lead and lift and as directed by the Engineer incharge of the work. (3D View)	Sqm	1
12	Table Top :Providing and fixing of **12mm corian** fixed with glue and buffing finished with all respect.Corian sheet.Including cost of materials, labour, instalation etc,. complete as per specifications..	Sqm	1
13	Table Top :Providing and fixing of **6mm corian** fixed with glue and buffing finished with all respect.Corien sheet.Including cost of materials, labour, instalation	Sqm	1

Sl.	Particulars	Unit	Qty
	etc,. complete as per specifications..		
14	Table units. Providing and fixing tables made up Of (commercial) 19mm plywood for Structure work back will be of 6mm plywood with Necessary supports & drawers. Drawers run by 20''hafele Telescopic channel & 19mm block board for doors.Door hang by S S Hinges,SS selected handle . Exposed surface finished with (1 mm thick laminate SF Shade)inner surface finished with liner laminates.cost including cost of materials, labour, instalation etc,. complete as per specifications & Drawings	Sqm	1
15	Manufacturing, supplying and fixing wooden ward robe of 0.60m deep using 19mm thick vinyl bonded water proof block board, shutters allround ward robe, lockable drawers with sliding channels, cupboard drapery hangers, curtain rods with end brackets, openable shutters with 19mm x 6mm thick plain teak wood beading, lipping 1.5mm thick commercial ply vertical support finished in approved 1.5mm lamination sheet of approved colour, shade and quality on all exposed surfaces. Inner surface painted with 2 coats of white synthetic enamel paint over 2 coats of Patti, one coat of wood primer, including cost of brass fittings, parliamentary hinges, C handles, tower bolts, magnetic catches, approved brand lock, adhesives, synthetic resins, nails, screws etc., complete including cost of all materials, labour charges, complete as per specification.& Drawings	Sqm	1
16	Design supply & installation of Glass partition designed to withstand the wind pressure as per IS 875 (Part-III). The Glass partition held with Fittings of SS-316 Grade Steel of approved manufacturer with glass panel having 12 mm thick clear toughened glass held together with SS- 316 Grade Stainless steel fixing assembly with laminated glass fins 21 mm thick. The Glass fins and glass panel assembly shall be connected to Slab/beams by means of SS- 316 Grade stainless steel brackets & Anchor bolts and at the bottom using SS channel of 50x25x2mm using fastener & anchor bolts, non staining weather sealants of approved make, Teflon/ nylon bushes and separators to prevent bi-metallic contacts, all complete to erform as per specification and approved drawings. The rate shall include all design, Engineering and shop drawing including approval from structural designer, labour, T&P, scaffolding, other incidental charges including wastage, enabling temporary services all fitting fixers nut bolts, washer,	Sqm	1

Sl.	Particulars	Unit	Qty
	Buffer plates, fastener, anchors, SS channel laminated glass etc. all complete.		
17	Supplying of good quality **Executive High Back Mesh** optium Chair of approved make With Head Rest with height adjustable handle.	Nos	1
18	Supplying of good quality **Imported Executive High Back Mesh** optium Chair of approved make With Head Rest with height adjustable handle.complete including cost of all materials, labour charges, complete as per specification.	Nos	1
19	Supplying of good quality Imported **Executive High Back Artificial leather** optium Chair of approved make With Head Rest with height adjustable handle. complete including cost of all materials, labour charges, complete as per specification.	Nos	1
20	Supplying of good quality **ALPHA MB Nylon Base** M05 Center Tilt Mech Arms Fxed of approved make With Head Rest with height adjustable handle. complete including cost of all materials, labour charges, complete as per specification.	Nos	1
21	Supplying of good quality **Steel Base** M05 Center Tilt Mech Arms Fxed of approved make With Head Rest with height adjustable handle.complete including cost of all materials, labour charges, complete as per specification.	Nos	1
22	Supplying and fixing of good quality **Auditorium push back chair** fixed with the chaneel with bolt system Tilt Mech Arms Fixed of approved make complete including cost of all materials, labour charges, complete as per specification.	Nos	1
23	Providing and fixing floor/wall mounted, **JAGUAR** white vitreous china single piece, double traps syphonic water closet of approved rand/make, shape, size and pattern including integrated white vitreous china cistern of capacity 10 litres with dual flushing system, including all fittings and fixtures with seat cover, cistern fittings, nuts, bolts and gasket etc including making connection with the existing P/S trap, complete in all respect as per directions of Engineer-in-Charge.	Nos	1
24	Providing and fixing **JAQUAR** wash basin with C.I. brackets, 15 mm dia CP Brass single hole basin mixer of approved quality and make, including painting of fittings and brackets, cutting and making good the walls wherever required: using White Vitreous China Wash basin size 550x400 mm with a 15 mm CP Brass single hole basin mixer	Nos	1

Sl.	Particulars	Unit	Qty
25	Providing and fixing **JAQUAR Single lever wall mixer** with L shaped Tubular bend set for overhead shower made of Stainless steel with all concealed fitting arrangements & all necessary accesories complete	Nos	1
26	Providing and fixing Temperature controlled **JAQUAR** Overhead rain showers with wall flange made of Stainless steel with all concealed fitting arrangements & all necessary accessories complete	Nos	1
27	Providing and fixing Single flow **JAQUAR** hand showers with Anti lime jets with Rain, Mist & Massage settings having 1.5m Extendable flexible tube and holder & wall flange made of Stainless steel with all concealed fitting arrangements & all necessary accesories complete - Class	Nos	1
28	Providing and fixing **JAQUAR** Bidet spray made of Stainless steel with all concealed fitting arrangements & all necessary accesories complete	Nos	1
29	Supplying and fixing of Table Pop Up Outlet, Desktop Pop Up Socket Center Countertop Socket Multimedia Strip Socket Connection Box Desktop with USB 3.0/2×HDMI / 2×AC/USB-A/USB-C/LAN for Conference Desk including labour for all items of work HOM of equipment etc., cost including cost of materials, labour, instalation etc,. complete as per specifications.	Nos	1
30	Providing and fixing ANTI SKID PVC VINYLE FLOORING of approved design and style , including cost of adhesive & all materials labour complete including cost and conveyance of all materials, labour for all items of work, HOM of equipment as per specifications and As per the direction of Engineer In-charge. with all lead and lift.	Sqm	1
31	Supplying and commissioning of Speaker It is a high-performance, full-range, surface mount loudspeaker designed for foreground and background music and speech reproduction in a wide range of installed applications. Features high output and 125° x 125° coverage pattern with a frequency range down to 70 Hz. Approved Model: Bose FreeSpace® DS 40SE or similar model in the preferred. Its Including Supplying, commissioning, testing, Programming and as per the direction of Engineer-In-charge.	Nos	1
32	Supplying and commissioning of Speaker It is a high-performance, full-range, Wall mount concealed loudspeaker designed for foreground and background	Nos	1

Sl.	Particulars	Unit	Qty
	music and speech reproduction in a wide range of installed applications. Features high output and 125° x 125° coverage pattern with a frequency range down to 70 Hz. Approved Model: Bose FreeSpace® DS 40SE or similar model in the preferred. Its Including Supplying, commissioning, testing, Programming and as per the direction of Engineer-In-charge.		
33	Supplying and commissioning of Digital Chairperson Discussion unit with removable microphone (30, 40, 50 or 70 cm). • Microphone connector • Microphone button, priority, next-in-line and volume control button • Built-in loudspeaker • Headphone connector • Cable of 2 meters included • D-MIC type microphone to be ordered separately	Nos	1
34	Supplying and commissioning of Digital Delegate Discussion unit with removable microphone (30, 40, 50 or 70 cm). • Microphone connector • Microphone button and volume control button • Built-in loudspeaker • Headphone connector • Cable of 2 meters included • D-MIC type microphone to be ordered separately	Nos	1
35	Supplying and commissioning of GSM immune gooseneck microphone of 40 cm with screwlock. Bi-color LED ring indication (red/green).Windscreen included (only for use with D-Cerno units)	Nos	1
36	Supplying and commissioning of Digital control unit with integrated recording capability for 50 D-Cerno units. • 4 digital RJ45 ports • Branch or loop connection (redundancy) • LAN connection for web server, camera control protocol or AES67 communication • 2 × USB-C for audio connection with UC or multi-channel recording • 2 × XLR OUT, 2 × XLR IN • 3.5 mm line-in and out • Plug and Play • Eco Power Safe mode • Power connector with locking • External power supply included	Nos	1
37	Supplying and commissioning of Connection cable, 10 m, black	Nos	1
38	Supplying and commissioning of Connection cable, 20 m, black	Nos	1
39	QuickFit™ 2-way 5¼" ceiling speaker with TwistFix™ grill, white version, 8Ω & 24 Watt @ 100V	Nos	1

Sl.	Particulars	Unit	Qty
40	Commercial mixer amplifier with 80W @ 4ohms / 100 / 70V	Nos	1
41	Video Conference Components: Supplying and commissioning of 1080p 60fps PTZ camera with 12× zoom, HDMI, USB and IP streaming. • 72.5° horizontal field of view • Simultaneous HDMI, USB & IP streaming output • Outstanding color reproduction	Nos	1
42	Supplying and commissioning of Multi-camera tracking device, supports up to 4 cameras of any OEM make, simple user-friendly interface No programming required,	Nos	1
43	Supplying and commissioning of cables, connectors, network switch and installation charges	Nos	1
44	Supplying and commissioning of 98-inch Crystal UHD signage display designed for professional environments such as boardrooms, classrooms and retail spaces with Quantum Processor 4K. Technical Specifications: • Panel Size: 98 inches (Diagonal) • Resolution: 3840 × 2160 (4K UHD) • Contrast Ratio: 5,000:1 • Viewing Angle (H/V): 178° / 178° • Video Inputs: 4 × HDMI 2.0 (HDCP 2.2) • External Control: RS232C • Dimensions (WHD): 2180.6 × 1243.9 × 48.4 mm • Processor: Quantum Processor 4K • Operating System: Tizen 6.5 • Power Supply: AC 100-240 V	Nos	1
45	Providing and Fixing of Brass Name Board, Cost Including Hetching, Stickering name, polish, labour transport for all items of work	Sqcm	1
46	Supplying and fixing plain sadarahalli granites benches of 4 feet length and I feet width with side arm support of 18" height with all leasd and lift and loading and unloading as per the direction of Engineer in charge of work.	Nos	1

TERMS AND CONDITIONS:

1. The agency shall quote the rate as per the specification and drawing prescribed.
2. The rate quoted shall be inclusive of all materials, labour, fabrication, transportation etc…, excluding GST
3. The quotations are invited for the purpose of budgetary offer for adopting rates in the estimate.
4. The agencies do not have any claim for entrustment of work.

5. Any other information shall be had from the office of the under signed during office hours or **Contact No.9845134433**
6. BBMP reserves right to accept or reject the quotation part or all without assigning any reasons.

-sd/-
Executive Engineer
MPED&Transport
Bengaluru Central City
Corporation

COPY SUBMITTED TO:-

1. Personnel assistant to Hon'ble Commissioner for kind information.
2. Additional Commissioner (Development)/ Special Commissioner (Finance) for kind information
3. Engineer – in – Chief for kind information.
4. Chief Engineer (Zone-2), BCCC for kind information.
5. CAO / Chief Auditor for kind information.
6. Public Relation Officer, BCCC for information and to publish in two leading National Newspapers in Kannada and English.
7. Notice board & Office Copy.

Executive Engineer
MPED&Transport
Bengaluru Central City
Corporation